

the European Spallation Source the next generation facility for materials research and life science

Cristina Oyón acknowledgements: Mats Lindroos, Steve Peggs

September 2009





OECD RECOMMENDATION

"A High Power Spallation Source in each Global Region"







ESS SITE SELECTION PROCESS

ESS is a research infrastructure in ESFRI (European Science Forum for Research Infrastructures) roadmap

- Three projects bidding for the site (Bilbao Spain, Lund- Sweden and Debrecen Hungary)
- Evaluation by ESFRI in 2008 by a Site Review Group
- Agreement on process to reach a site decision within the fringes of the European Competitiveness Council
- Core group for ESS formed (14 countries) and decision on site at a Ministerial meeting in Brussels (28 May)
 - Sweden proposed as ESS site with important contributions and supporting infrastructure in Spain
- Integration of ESS-B and ESS-S accelerator and target teams
- First ESS Steering Committee meeting in Copenhagen 22-23 October 2009





ESS FIRST STEPS

- ESS-S and ESS-B have become ESS which now has 12 future member states
 - Main site for facility in Lund in Sweden and complementary infrastructure in Bilbao in Spain
- ➢ First neutrons for 2019 with full design specifications in 2023
 - Ambitious goals requires ambitious planning
- Build on latest SC RF R&D
 - Requires high reliability and low losses
- Maximize synergies with other similar projects
 - Cost and time gains
 - Trained people are in short supply
- Very challenging task...
 - ➤ That is our job...
 - …and that is why we are here!





FACILITY TECHNICAL OBJECTIVES


5 *MW* Long pulse source ≤2 ms pulses ≤20 Hz Protons (H+) Low losses High reliability >95%












Facility investment: 1.377 M \in_{2008} with 22 instruments + 101 M \in_{2008} site specific cost Operational cost: 89 M \in_{2008} per year Decommissioning cost: 344 M \in_{2008}



DESIGN UPDATE


ESS-Bilbao preparatory work



The ESS-B workshop held in Bilbao in March 2009 brought together more than 160 experts from across the world, leaders in the fields of high power proton accelerators, beam dynamics and targets, in a format and infrastructure that promoted open discussion, while maintaining the focus of documenting clear recommendations for future collaborative R&D efforts.







In comparison to the originally proposed design (5 MW, 1 GeV, 150 mA, 16.7 Hz) <u>the parameters have been modified</u> in order to **simplify the linac design** and to **increase reliability**. In essence the current has been decreased and the final energy has been increased, keeping the footprint of the accelerator the same.

- Increase in energy With increased energy the average pulse current can be reduced by the same factor.
- Increase of the cavity gradient By decreasing the current to 75 mA, the gradient can be raised to 15 MV/m, keeping the coupler power constant at 1.2 MW.
- ✓ Increase of beam energy the final energy was increased from 1 to 2.2 GeV.
- Repetition rate The originally proposed repetition rate of 16.67 Hz has been increased to 20 Hz.
- ✓ **Pulse length** The originally proposed pulse length of 2 ms has been reduced to 1.5 ms





Work with expert group (the ESSS linac reference group)




Table 1: Primary ESSS performance parameters in the long pulse conceptual design. There is no accumulator ring.

INPUT		Nominal	Upgrade
Average beam power	[MW]	5.0	7.5
Macro-pulse length	[ms]	2.0	2.0
Pulse repetition rate	[Hz]	20	20
Proton kinetic energy	[GeV]	2.5	2.5
Peak coupler power	[MW]	1.0	1.0
Beam loss rate	[W/m]	< 1.0	< 1.0
OUTPUT			
Duty factor		0.04	0.04
Ave. pulse current	[mA]	50	75
Ion source current	[mA]	60	90
Total linac length	[m]	418	418





Question for future users and ESS technical teams:

- How long is the ideal "long pulse" and what is the ideal repetition rate?
- Can the neutron pulse be shaped in a more useful shape for physics through shaping of the proton pulse?
- Can we confirm that the neutron intensity at the instruments is constant per MW up to a certain energy? (< 3 GeV)
- What flexibility can be left in the design for future upgrades without compromising construction time, schedule and budget?
- Using the best SCRF technology, what is the optimum design of the linac with given objectives?





Work Packages (work areas)

- 1. Management Coordination
- 2. Beam Physics
- 3. Infrastructure Services
- 4. SCRF Spoke cavities
- 5. SCRF Elliptical cavities
- 6. Front End and NC linac
- 7. Beam transport, NC magnets and Power Supplies
- 8. RF Systems





ESS- BILBAO WHERE ARE WE HEADING TO?

Spain and Sweden have signed an agreement that formalises a **joint candidature** between both countries for the development of ESS

The agreement establishes the bases for a unique project, with **two centres**: the main centre in Lund and another in Bilbao, which shall contain an important complementary infrastructure of the main one.

ESS- Bilbao previous organization is now nucleating **a stable R&D centre** focusing on the production and use of light-ion beams for research purposes as well as **a remote experimental and educational centre** for materials science research.

We view such a development as a cornerstone for our significant participation within several ongoing projects (ESS, IFMIF, FAIR...),

The development of the Bilbao Centre represents a **significant investment of 180 M€** by the Spanish government and Basque Government starting in 2009.






ESS- BILBAO STRATEGIC OBJETIVES

- 1. Technology development
 - R&D, prototyping and testing of technologies related to the construction and operation of research infrastrutures
- 2. Knowledge transfer to industry
 - ✓ Validation infrastructure for accelerators components
- 3. Science performance improvement
 - Remote access for experimentation
 - Dissemination and outreach activities





ESS- BILBAO FACILITY DEFINITION







ESS- BILBAO TECHNICAL OBJECTIVES

- **Phase 1**: Build a proton injector following the performance expected for ESS, also able to run beams of deuterons with moderate current (5 mA or so)
- Phase 2: Build and commission accelerating structures (RFQ+ DTL or SC cavs) able to reach 40- 50 MeV for protons. Extract a proton beam for materials/ radiation biology applications.
- Phase 3: Set up a test bench for SRF structures (cavities + cryomodules) able to carry out tests of SRF cavities with beam. Provide acceleration up to 150 MeV / 200 MeV (H⁺) and extract a beam for applications purposes.





ESS- BILBAO ONGOING PROJECTS

ECRIS - at present under design. Expect to start next January, extracting a H⁻ beam from an ISIS-like Penning source

LEBT - Two solenoid structure. Design based upon that developed within the MICINN-ISIS collab. Capability to chop the beam to reduce the rise time.

RFQ - Structure composed by three resonantly-coupled cavities operating at 352.2 MHz, able to bunch and accelerate a beam up to 5 MeV with transmission better than 90% and emittances better than de 0.2" mm.mr (norm. rms) en transverso y 0.2" grad MeV (rms) long. Reference designs (for the time being) LEDA, Linac4 and ISIS-FETS. A first prototype of a LLRF module built within our premises will be ready in 2 months.

MEBT · Composed by a set of focusing quads plus re-bunching cavities and diagnostics equipment. Detailed design will depend upon operational results after chopping experiments with the LEBT chopper.

Beam Dump - A prototype able to stop a 5 MeV /2 MW beam already under construction. Planning to develo something sturdier.





ESS- BILBAO ONGOING PROJECTS

Development of Distributed Control and Remote Handling Systems - Already started to implement Networked Control Systems (NCS), based upon the EPICS standard.

Beam Dynamics - Results from multiparticle (tracewin & track) simulations already available.

Power Klystron - Negotiations to develop a 1.3 MW pulsed klystron (352.2 MHz). A high power HVCM already beind under development in collab. with SNS.


Low b Spoke Cavities - A EM design already available. Activities to test them on cold models already ongoing. Nb prototypes to be built within an agreement with ACS- France.

Target – Rotating target design studies in collaboration with SNS. First prototype to be built and tested during 2010





PREPARATORY WORK FOR THE DESIGN UPDATE



Workshop Conclussions Report







NEXT STEPS



Definition of detailed objectives

✓ Facility definition

Facility construction plan

Legal aspects and organisational definition

✓ Team building

Budget plan definition



