


# The CLIC Linear Collider

*Hans H. Braun / CERN*

- Introduction CLIC & CTF3
- CTF3 status and achievements
- RF Structure tests
- Future plans and selected open issues
- Conclusions



## **CLIC goal**

*Develop technology for  $e^-/e^+$  linear collider with  $E_{\text{CMS}} = 3 \text{ TeV}$*

## **CLIC physics motivation**

*"Physics at the CLIC Multi-TeV Linear Collider :*

*report of the CLIC Physics Working Group," CERN report 2004-5*

## **Next CLIC milestone**

*Demonstrate key feasibility issues by 2010*


# LHC

- Physics start-up 2008
- $E_{CMS}=14$  TeV proton on proton
- Very first physics analysis results from experiments expected for 2010




Descent of the  
last LHC magnet  
26 April 2007

## Overall view of the LHC experiments.




Protons are composite objects



Only fraction ( $\approx 1/6$ ) of total proton energy  
available for collision of constituents

$\Rightarrow$  A Lepton collider




needs

$$E_{CMS} \geq 14 \text{ TeV} / 6 = 2.3 \text{ TeV}$$

to cover the energy range of LHC

## My simplistic view on the future of accelerator particle physics at the energy frontier



## **BASIC FEATURES OF CLIC**

- High acceleration gradient



- “Compact” collider - 3 TeV with overall length < 50 km
- Normal conducting accelerating structures
- High acceleration frequency

- Two-Beam Acceleration Scheme



- Cost-effective & efficient
- Simple tunnel, no active elements

- Central injector complex

- “Modular” design, can be built in stages

# CLIC TWO-BEAM SCHEME

- Drive beam
- High current
  - Low decelerating field

QUAD

QUAD

POWER EXTRACTION AND  
TRANSFER STRUCTURE (=PETS)

RF


ACCELERATING  
STRUCTURES

- Main beam
- Low current
  - High accelerating field

BPM

4.5 m diameter

CLIC TUNNEL  
CROSS-SECTION



## Recent changes of key CLIC parameters

*Main Linac RF frequency*

**30 GHz  $\Rightarrow$  12 GHz**

*Accelerating field*

**150 MV/m  $\Rightarrow$  100 MV/m**

*Overall length @  $E_{CMS}=3\text{ TeV}$*

**33.6 km  $\Rightarrow$  48.3 km**

### **Why ?**

Very promising results of earlier 30 GHz Molybdenum test structures (190 MV/m) not reproduced for test conditions closer to LC requirements (i.e. long RF pulses, low breakdown rate, structures with HOM damping)

Copper structure tests don't indicate advantage of frequencies  $>12\text{ GHz}$  for achievable gradient

Parametric cost model indicates substantial cost savings for 12 GHz/100 MV/m (flat minimum for this parameter range)


Allows RF structure testing in existing SLAC and KEK facilities

Increase chance of feasibility demonstration by 2010



100 MV/m is lowest permissible gradient for a 3 TeV machine in Geneva region




# CLIC RF power source



## Drive beam time structure - initial





## Drive beam time structure - final




## RF parameters CLIC compared with NLC

		<b>CLIC</b> <b>12 GHz, 100 MV/m</b> <i>preliminary</i>	<b>NLC</b>  <i>as for ILC-TRC 03</i>
Loaded Accelerating Gradient	MV/m	100	50
Frequency	GHz	12	11.4
Structure iris aperture radius $a/\lambda$	1	0.155-0.0852	0.21-0.148
Structure length	mm	229	900
Structure input power	MW	76	75
Pulse length	ns	300	400
Bunch charge	$e_0 \times 10^9$	5.2	7.5
Bunch separation	rf cycles	8	16
Beam current	A	1.25	0.86
RF to beam efficiency	%	28.8	31.5
Rep. rate	Hz	50	120
No. Klystrons per TeV	1	264	8256
Klystron frequency	GHz	1.33	11.4
Klystron peak power	MW	33	75
Klystron RF pulse length	$\mu\text{s}$	140	1.6
Average power per klystron	kW	231	14.4




**CLIC 3 TeV**

not to scale



# Main/Drive Beam Injectors and Experimental Area Layout



connections to common transfer tunnel (Ø 3.8m)

e- e+ beam tunnel = 170 m

drive beam tunnel = 140 m


common transfer tunnel (Ø 4.5m)

324 + 10 = 334m

final transfer tunnels (Ø 3.8m)

e- beam tunnel = 901 m

e+ beam tunnel = 971 m






## ***Motivation and Goals of CTF3 collaboration***

- Build a small-scale version of the CLIC RF power source, in order to demonstrate:
  - **High efficiency full beam loading** accelerator operation
  - electron beam **pulse compression and frequency multiplication** using RF deflectors
- Provide the **RF power** to test the CLIC accelerating structures and components
- ***Tool to demonstrate until 2010 CLIC feasibility issues identified by ILC-TRC in 2003***

# CTF3 layout

Drive Beam Injector

Drive Beam Accelerator, 150 MeV



30 GHz  
High Gradient  
Test stand

8 x I.B. 8 x I.B.

X 4  
Combiner Ring  
84 m

CLEX


Drive beam stability bench marking


Decelerator Test Beam Line

12 GHz Two-Beam Test stand  
& Linac subunit

CLIC sub-unit


200 MeV Probe Beam  
Injector





## CTF3 build by a collaboration like a particle physics experiment

*commissioned with beam*



## CTF3 collaboration official members

Country	Institute
20 member states	CERN
Finland	Helsinki Inst. of Physics
France	DAPNIA
	LAL
	LAPP
India	BARC
	RRCAT
Italy	LNF
Pakistan	NCP
Russia	BINP
	IAP
	JINR
Spain	CIEMAT
	IFIC
	UPC
Sweden	Uppsala University
Switzerland	PSI
Turkey	Ankara Universities
USA	NWU
	SLAC

collaboration board

chairman  
*M. Calvetti / LNF*

spokesperson  
*G. Geschonke / CERN*




# Some impressions from CTF3




Linac



Delay Loop



Beam up to here




30 GHz RF power testing

Transfer Line TL1 and Combiner Ring





# Fully beam loading operation in CTF3



theoretical RF-to-beam efficiency: 96%



CTF3 Drive Beam Acc. Structures (3 GHz) – SICA (Slotted Iris – Constant Aperture):

- 32 cells
- 1.2 m long
- $2\pi/3$  mode
- 6.5 MV/m av. acc. gradient for 3.5 A beam current
- HOM damping slots



## Full beam loading operation in CTF3 – Demonstration for CLIC operation

Setup: Adjust RF power and phase and beam current, that fully loaded condition is fulfilled





Precise measurement of

- beam current,
- beam energy in spectro 4 and spectro 10
- RF structure input power


**Measured RF-to-beam efficiency: 95.3 %**  
**Theory: 96% (~4 % ohmic losses)**

# How does the bunch frequency multiplication work?

CTF3 Injector with 3 SHB cavities (1.5 GHz)



Phase coding and bunch frequency multiplication in delay loop




Beam combination  
with transverse  
RF deflector

# Commissioning of the Delay Loop – SHB system


Key parameters for the SHB system: 1) time for phase switch < 10 ns (15 1.5 GHz periods)  
2) satellite bunch population < 7 %  
(particles captured in 3 GHz RF buckets)

## phase switch:




Phase switch is done within eight 1.5 GHz periods (**<6 ns**).

## satellite bunch population:




Satellite bunch population was estimated to **~8 %**.






## Beam recombination in the Delay Loop (factor 2)



Present CTF3 run: Combiner Ring commissioning  
Status: half way round



**CERN:** Layout, infrastructure, cabling, magnets, power supplies, installation

**CIEMAT:** Septa magnets, sextupoles, correctors, extraction Kickers

**INFN:** RF deflectors, wiggler, vacuum chambers, BPM (BPI)

**LAPP:** BPM electronics

**LURE:** quadrupoles

**BINP:** magnet realization

*two weeks ago 1<sup>st</sup> beam transport  
through half of the ring,  
from injection to extraction*

## Summary of recent CTF3 Achievements

- Nominal beam production and stable acceleration of 3.5 A beam with full pulse length without significant emittance growth. Wakefields kept under control with HOM damping+detuning and strong transverse focusing.  
Measured performance is consistent with predictions from beam dynamics simulations.
- Measured RF power to beam energy transfer efficiency of 95% in fully loaded operation for normal conducting linac !  
Proves that drive beam production is as efficient as predicted.
- Demonstration of bunch frequency multiplication with delay loop using RF deflector cavities and phase coding with rapidly phase switched subharmonic buncher. This is a key ingredient to achieve bunch train compression.
- Routine 24h, 7 days a week operation of fully loaded linac for 30 GHz production  $\Rightarrow$  fully loaded operation can be very reliable and stable.



## CLIC Accelerating structure test facilities

### Operational

- 30 GHz structures, CTF3 linac test stand  
(no commercial high power power source at this frequency)
- 12 GHz structures. Klystrons of SLAC-NLCTA (actually at 11.4 GHz)

### Future plans

- From 2009 12 GHz test capabilities in CTF3 CLEX two beam test stand TBTS will also test the decelerator prototype for the drive beam decelerator
- Testing at KEK facilities ?
- A 12 GHz klystron based test stand at CERN for late 2009 is presently under discussion in collaboration with several European FEL projects who intend to use X-band acceleration.

## Some remarks about CLIC parameter change and CTF3

Bunch repetition frequency of drive beam can be readily chosen as 6, 9, 12, 15 GHz by varying number of stacking turns in combiner ring and fine tuning of ring circumference with wiggler.

Drive beam can produce RF on any harmonic of these frequencies.



This makes adaptation of CTF3 drive beam to new frequency straight forward !

Definitive frequency choice was urgent, since ordering of RF components for CLEX two beam test has to start now.


## 30 GHz RF source in CTF3

CTF3 linac beam at mid linac point  
 $I_{beam}=5$  A,  $T=90$  MeV is decelerated  
in PETS (=power extraction and transfer structure)


70 MW, 400 ns, 1-50 Hz available for  
structure testing




**Present RF power test of CLIC 12 GHz (actually 11.4 GHz)  
prototype structure at NLCTA (SLAC)**



RF conditioning curve of presently ongoing test at SLAC-NLCTA of existing SLAC NLC 11.4 GHz prototype "T53vg3" with CLIC type parameters







To achieve 300 ns pulse length at 100 MV/m still a lot of progress required. Improvements expected from new shorter structures with less peak power flow. Alternatively pulse length can be reduced at expense of power efficiency.




## Power extraction and transfer structure PETS

Extracts 140 MW of power from 95 A drive beam  
to feed two main beam accelerating structures



Output coupler



Will be tested in CTF3 two beam test stand from late 2008 on

## Functionality and Specifications for TL2 (commissioning spring 2008)


Transport of drive beam from combiner ring extraction to CLEX

Bunch length manipulation with  $R_{56}$  variable in the range  $-0.35\text{m} < R_{56} < 0.35\text{m}$ , with compensated  $T_{566}$ .

Emittance dilution  $< 10\%$  (for 150 MeV,  $e_{x,y}=100$  mm)


Vertical achromat for 50 cm vertical displacement to adapt for different floor level of CLEX relative to EPA building

“Tailclipper” consisting of a fast kicker plus a collimator dump to adjust beam pulse length for drive beam in two beam test stand and TBL





# CLEX building



**Construction on schedule**  
**Equipment installation starts this month (May 2007)**  
**First beam to CLEX in spring 2008**

## **CLEX Glossary**

**CLEX**=CLIC EXperimental area

**TBTS**=Two Beam Test Stand

Testbed for 12 GHz RF tests of drive beam decelerating structures (PETS) and main beam accelerating structures.

Demonstration of two beam acceleration

**TBL**=Test Beam Line

Feasibility demonstration of CLIC drive beam decelerator

**CALIFES**=Concept d'Accélérateur Linéaire pour Faisceau d'Electrons Sonde  
3 GHz probe beam injector to simulate main beam in TBTS


**TL2'**

switchyard for drive beam and drive beam diagnostics

**ITB**=Instrumentation Test Beam

Option for 2<sup>nd</sup> beamline connected to CALIFES for development and test of beam diagnostic equipment

## Layout of CLEX-A (A=Accelerator housing) floor space



## Space reservations

<b>CALIFES</b>	23.2 m from cathode manipulator arm to exit flange of spectrometer
<b>TBTS</b>	16.6 m from output spectrometer to end of beam dump
<b>TBL</b>	31.4 m from dogleg bend to end of beam dump
<b>ITB</b>	16.0 m from 2 <sup>nd</sup> dogleg magnet to end of beam dump (optional, not funded yet)


# 180 MeV Probe Beam Injector



**ALIFES** = Concept d'Accélérateur Linéaire pour Faisceau d'Electrons Sonde

choice of architecture :

- 1 photo-injector
- 3 LIL sections: 1 for compression and 2 for acceleration
- 1 beam line with diagnostics (leading to 2-beam teststand)





RR-2007/01/15

16.5 m

drive beam

probe beam

0.75 m

PETS

accelerating structure

waveguide

chicane for measurement breakdown current

corrector dipole

spectrometer dipole

quadrupole triplet

BPM

OVR screen

Faraday cup

silicon detector

beam dump

bellows

gate valve

shielded gate valve

pumping port w/ valve

shielded pumping port w/ valve

Pirani gauge

Penning gauge


ion pump 40 l/s

## CTF3 Drive Beam RF Gun



Test set-up for 2008

If successful this gun will replace  
thermionic gun of drive beam linac

Phase coding will then be performed with  
pockel cell switching of laser beam instead  
of presently use subharmonic cavities



## CTF3 Probe Beam RF Gun




PHIN

## CTF3 Laser system

Drive photocathode of future CTF3 drive beam linac  
RF gun, 2332 bunches of 2.3 in 1540 ns,  
rep. Rate 1-50 Hz. Stability goal  $10^{-4}$

Another 140 ns train is picked from the pulse train  
for RF gun of probe beam RF gun me





# CERN installation

Amplifier 2

Amplifier 1

Preamplifier

Pulse slicing  
Pockels cell

Oscillator


Fiber-optics coding system






Amplifier 1

Amplifier 2




# POCKELS CELL (PC) INSTALLATION



Beam propagation  
direction (output)

BUT no beam

Brewster plate




Brewster plate

Beam propagation  
direction (input)

Beam propagation  
direction (output)


BUT beam

Brewster plate



Brewster plate

Final beam spot after  
PC, AMP2 off, AMP1  
90A



Power:

Gate: (390 -> 400) us → 0.14W  
→ ~2.8 KW

Some open CLIC and CTF3 R&D items

## Non interceptive beam profile monitors

Drive beam emittance monitoring:


typical rms beam size 1 mm, beam current 5-100 A

Main beam emittance monitoring:

Length of diagnostic section is determined by limit of laser wire technology.

Strong interest to measure beam size in 100 nm-1 $\mu$ m regime (not only from CLIC)

### Diagnostics optics & layout



This is for existing laser wire technology  $\sigma_y > 1\mu\text{m}$

If new BSM measures  $> 0.4\mu\text{m}$ , length  $\approx 400\text{m}$ .




52 beam dumps for drive beam required


$E_{beam} \approx 300 \text{ MeV}$ ,  $P_{average} = 300 \text{ kW}$  each

6 main beam dumps,

$E_{beam} \approx 1500 \text{ GeV}$ ,  $P_{average} = 20 \text{ MW}$  each



TJNAF  
type dump ?



## Some examples of CTF3 beam physics and operation issues

Control of longitudinal dynamics is essential to get time structure of drive beam. CTF3 compressor/stretcher chicane, delay loop, combiner ring and TL2 are all equipped with sextupole families to assure isochronous condition up to 2<sup>nd</sup> order in  $\Delta P/P$ . But effect of sextupole correction has not been studied with beam due to lack of manpower.

Delay loop together with upstream compressor/stretcher chicane is an ideal test bed to measure energy loss due to CSR. Has not been studied due to lack of manpower.


## **$e^+$ and $e^-$ source**

Requirement:  $>2$  A beam current for 300 ns with 50 Hz repetition rate

Ideally both  $e^+$  and  $e^-$  polarized


Some studies have been performed for a CLIC Compton source of polarised positrons, but CLIC relies mainly on past NLC R&D

# Recently collaboration contract with BINP for development of SC wiggler magnets for CLIC damping ring



Optimum wiggler field strength equilibrium emittance as a function of wiggler period length.

		Permanent magnet	Super conducting (NbTi)
Period length	cm	10	5
Total height of beam aperture	mm	12	12
Peak field on axis	T	1.7	2.5
Length of wiggler module	m	2	2
Transverse field flatness at +/-1cm	%	<0.1	<0.1
Operating temperature	K	Room temperature	4.2 K





## Conclusions & outlook

- New CLIC parameters to adapt to recent structure tests and results of cost optimizations.
- CTF3 installations and machine experiments on schedule (almost) for feasibility proof by 2010
- Organization of CTF3 as an international collaboration modeled after big particle physics experiment works astonishingly well. Opening CTF3 collaboration to CLIC subjects beyond CTF3 under discussion.

## Upcoming CLIC related events

- Workshop on X-band accelerating structures and power sources, CERN June 18-19
- First meeting of CLIC ACE international advisory committee, CERN, June 20-22
- IBS Mini-workshop, Cockcroft Institute/UK, August 28-29
- 1<sup>st</sup> Workshop on CLIC machine and detector issues, CERN, provisional date October 15-17
- 12<sup>th</sup> CTF3 collaboration meeting, CERN, ~ mid January 2008