



Ed. Ciapala, Erk Jensen

Jefferson Lab Seminar

August 2012





- SRF systems at CERN
- Approved projects now under way at CERN
- SRF infrastructure and facilities upgrade
- SRF Diagnostics and R&D
- New SRF projects under study
- Summary / Conclusions



The LHC RF system at IP4





LHC Cryomodules in RUX45

Basic parameters:

- 8 SC single cell cavities per beam, total 16 cavities in 4 cryomodules at IR4
- Need to handle very high beam currents LHC nominal beam is 0.56 A d.c.
 - LHC could go up to twice nominal..
- Low R/Q: 44 Ω (Low Z at high Q_{ext})
- Technology: Nb sputtered on Copper as LEP
- 2 MV nominal per cavity, 5.5 MV/m nominal gradient
- Conditioned to 50 % higher prior to their installation in LHC Could just reach max. 11 MV/m in test
- Variable power coupler, 11,000 < Q_{ext} < 200,000 => High bandwidth at injection for damping of injection transients / higher voltage during physics
- High power handling of coupler (> 300kW)
- One klystron per cavity, rating 330 kW

Performance has been good, but currently one cavity runs at reduced gradient. Repair planned during LS1





- SRF systems at CERN
- Approved projects now under way at CERN
- SRF infrastructure and facilities upgrade
- SRF Diagnostics and R&D
- New SRF projects under study
- Summary / Conclusions







- Variable energy between 1.2 and 10 MeV/u
- 32 SC QWR (20 @ β =10.3% and 12@ β =6.3%)





- A string of 6 cryo-modules:
 - 4 cryo-modules with 5 high-beta cavities + ancillaries (first phase – Energy upgrade)
 - 2 cryo-modules with 6 low-beta cavities + ancillaries (second phase – Intensity upgrade)

Low QWR (left) and high QWR (right).

- Technology is Nb sputtered on Cu
- First cavities being tested learning process, collaboration with INFN Legnaro

QWR workflow, tests in 2012

W. Venturini







W. Venturini

Prototype cavities Jan-Jul 2012



	May-12	Jun-12	Jul-12	Aug-12		
Coating Resistiv Coating <mark>s</mark>	ve heating inside the antenna Q3_1	Copper screens, IR lamps, 8 kW I	Power supply Q1_11	QP1		
RF tests	Q2_6	Q3_1 Cryo Slv	118 dowr <mark>Q3_1 + M</mark> agnet	Q1_11		



W. Venturini

Cavity performance





W. Venturini

Planning for Cavity Production

	Aug-12	Sep-12	Oct-12	Nov-12	Dec-12	Jan-13	Feb-13	Mar-13	Apr-13	May-13	Jun-13	Jul-13	Aug-13	Sep-13	Oct-13	Nov-13	Dec-13
Q1																	
Q2																	
Q3		*															
QP1	*	*	*	*													
tests in SM18	1	2	1	1					2	2	2	2	2	2	2	2	
tests in IPN						1	2	1									
Copper billets	2	2	4	2	IT		2	2	2	2	2						
CATE substrates				1	2 *	2											
Purchased subst	rates		IT			1	2	2	2	2	2	2	2				
Coating series						2	2	2	2	2	2	2	2	2	2		
RF tests series ca	avities						2	2	2	2	2	2	2	2	2	2	
																→	
СМ										New CR C	.M1 Test As	s.	CM1 A	CM1 A	CM1 A/RF	CM1 RF	CM1 RF
						Dreduction of 00 condition in 0040											
						Production of 20 cavilies in 2013											





- A beam of closely spaced bunches requires non-zero crossing angle at the IR to avoid parasitic collisions and to reduce beam-beam effects
- With non-zero crossing angle, luminosity gain by squeezing beams further is small (red curve below).





- Crab cavities can compensate for this geometric effect by tilting the bunch giving a luminosity increase of about 50 % at β* of 25 cm.
- In addition, crab cavities provide an ideal knob for luminosity levelling;
- This allows optimizing for **integrated** rather than peak **luminosity**!





Novel designs to fit tight space requirements in IR1 and IR5

		Double Ridge (ODU-SLAC)	4-Rod (UK)	¹ ⁄4 Wave (BNL)	104
rical	Cavity Radius [mm]	147.5	143/118	142.5/122	
ometr	Cavity length [mm]	597	500	330-405	B1 B2
e	Beam Pipe [mm]	84	84	84	
	Peak E-Field [MV/m]	33	32	43	< 50 MV/m
	Peak B-Field [mT]	56	60.5	61	< 80 mT
R	$R_{_{T}}/Q$ [Ω]	287	915	345	
	Nearest Mode [MHz]	584	371-378	657	
		T	Ť		

Prototypes of these cavities to be tested this year





• Courtesy: J. Delayen (JLAB ODU), Niowave Inc.







May 2012



SRF Activities at CERN - JLAB Aug 2012





• Courtesy G. Burt (Lancaster)





Nb rods from solid Ingot via EDM (significant material saving)





Finished cavity at Niowave





• Courtesy I. Ben-Zvi et. al (BNL)



.uminosity **Testing of Compact Cavities and Cryostats**



- Ultimately, installation of 8 crab cavity modules around IR1 & IR5 (2022-23?)
- Complete validation and test of compact CCs in a complete cryomodule with beam in SPS in 2016 ٠
- SPS working group was recently set up for a complete study (A. Macpherson) ٠
- Test in LHC IR4 would follow in 2017... (just before Long Shutdown LS2) ٠

High

HC







Seen as a high priority collaboration with US & European partners

- ODU-Niowave: Phase I SBIR for a test cryomodule approved
- LARP Collaboration:

FNAL has made a proposal on CM development to DOE, positive recommendation from the recent DoE LARP review:

- "Develop a realistic plan tor testing crab cavities in the SPS"
- "Start immediately on the specifications and design of a cryomodule".
- Actions (R. Calaga's presentation at the review)
 - Develop initial concepts in 6-8 months (FNAL, SBIR, Triumph, CEA-CNRS)
 - Immediate task is to identify specific SPS constraints (environmental & RF)
 - Crab Engineering Meeting will be held 13-14 Dec. 2012 at FNAL







- LP-SPL: SC-linac (160 MeV to 4 GeV) with ejection at intermediate energy
 - High gradient: <u>25 MV/m at 704 MHz</u> in β = 1 section.
 - Part of the upgrade of the CERN injectors, with PS2
- HP-SPL: High Intensity Higher Energy SC-linac (160 MeV ® 5 GeV)
 - Longer duty cycle
 - New klystron modulators, upgraded infrastructure (cooling & electricity, etc.)
 - 5 additional β = 1 cryomodules to reach 5 GeV (π production for v Factory)







In 2010, original upgrade plan for LHC injectors abandoned However, program launched for **study of SC RF for high intensity proton driver** in the context of possible future neutrino facilities at CERN.

- Included in CERN MTP, with resources.
- Comprises:
 - Continuation of design work on HP-SPL, excluding integration & site specifics.
 - Includes prototyping of critical components: high gradient cavities, RF ancillaries and the construction of a 4-cavity test cryomodule
 - Upgrade of clean room and assembly facilities at CERN
 - Preparation of a power test stand
- Plan to power test the cryomodule in 2014 (CERN SM18)
- Updated CERN yellow report on SPL to be completed by mid 2012
 - SPL documentation in EDMS [<u>https://edms.cern.ch/nav/SLHC-000008</u>]
 - SPL (SLHiPP) meetings in Indico [<u>http://indico.cern.ch/categoryDisplay.py?categId=1893</u>]



SPL 704 MHz Prototyping



- Collaboration with CEA Saclay Cavity design by Saclay
- Low β protos built & tested at CEA
- Tuner design & construction by Saclay
- He tank & cryomodule designs ongoing (CEA/CERN)
- Four β = 1 5-cell cavities being made in industry
- Cryomodule working group doing CM design
- 704 MHz klystron ordered, power systems being prepared for SM18 power testing
- Close collaboration with European Spallation Source (ESS) in Lund











BNL 704 MHz cavity (20 MV/m with high Qo demonstrated)





- First industrially produced cavity just received from Research Instruments
- Will be treated, rinsed and tested at CERN
- First of 5 5-cell cavities expected end of 2012
- Bead pull, tuning system and diagnostics being prepared.
- Hopefully a test can be done before the SM18 Cryo system shut down at the end of the year...
- Comparison of results with other Labs for cavities in this frequency range is of interest
- Synergy with LheC and eRHIC....







- SRF systems at CERN
- Approved projects now under way at CERN
- SRF infrastructure and facilities upgrade
- SRF Diagnostics and R&D
- New SRF projects under study
- Summary / Conclusions



SC cavity assembly and testing at CERN



 CERN SCRF Installations in SM18 date from 1990s and LEP, with minor refurbishing for the LHC cavities





- For new projects, a major upgrade of facilities is in progress to handle modern <u>high gradient</u>, <u>high Q cavities</u>:
 - New HP rinsing equipment & UP water for preparation of cavities and components
 - New clean rooms
 - Improved cryo, upgrade of low efficiency line, and 2K operation
 - Modern diagnostics equipment
- Not intended for Large Scale production...
 - Advice from other Labs, e.g. DESY, SACLAY, BNL, Fermilab & JLAB gratefully acknowledged



SRF Clean Room Upgrade in SM18









- SRF systems at CERN
- Approved projects now under way at CERN
- SRF infrastructure and facilities upgrade
- SRF Diagnostics and R&D
- New SRF projects under study
- Summary / Conclusions





K. Liao

- Temperature Mapping
 - "Octopus" flexible kapton PCB fits around the cavity in 2 halves
 - Using Allen Bradley resistors with exact calibration in microprocessor system
 - 560 resistors on a single cell SPL cavity
 - 3000 on 5-cell cavities



- Second Sound Diagnostics
 - Using OSTs (Oscillating Superleak Transducers)
 - Tests on sensor design in cryolab
 - Used in SPL single cavity tests 28
 OSTs
 - Trying to get results that are more precise & consistent
 - 64 OSTs on 5-cell cavity







(W. Weingarten) T. Junginger, S. Aull

MOTIVATION

- Power consumption in a superconducting cavity is proportional to its surface resistance R_s
- R_s shows a complex behavior on external parameters, such as temperature, frequency, magnetic and electric field

$$P_{\rm c} \propto R_{\rm S}(f,T,B,E)$$

Some Open Questions:

- Origin of the residual resistance
- Origin of the Q-Slope/Q-drop
- Stronger Q-Slope of niobium films compared to bulk niobium
- Influence of magnetic and electric field
- Influence of the surface properties





Enables RF characterization of small samples over a wide parameter range

- Resonant frequencies: 400MHz, 800MHz, 1.2 GHz
- Almost identical magnetic field configuration
- Ratio between peak magnetic and electric field proportional to frequency





- Sample diameter: 75mm
- The sample needs to be EB-welded to the sample cylinder
- Bulk niobium and copper samples are available





Calorimetric and trapped field measurements

By mounting DC heaters and coils in the cylinder below the sample the QR has allowed measurements on various materials and with different qualities:

- Rs(B,T,f),
- penetration depth
- quench field (High T)
- thermal conductivity and RRR and studies on the influence of trapped magnetic flux

(Sarah Aull, 2012 Thin Films Workshop – JLAB)

Future Work

- Production of HIPIMS Sample (CERN)
- Current bulk Nb sample: Diffusion of N to produce NbN (INFN)
- MgB₂ (AASC) currently surface (CERN) and composition (HZB) measurements; DC critical field measurements (CERN) being planned









- SRF systems at CERN
- Approved projects now under way at CERN
- SRF infrastructure and facilities upgrade
- SRF Diagnostics and R&D
- New SRF projects under study
- Summary / Conclusions





60 GeV 100 mA electron ring in the LHC tunnel:

- 560 MV, 721.42 MHz cw RF
- 112 two cell cavities at 11.9 MV/min
- * 14 cryomodules of ~ 10 m, 8 at CMS and 3+3 at ATLAS
- One 1 MW klystron feeding 2 cavities, 56 total
- One 6 MVA Power Converter per 4 klystrons on surface
- Total 49 MW klystron RF power, 79 MW grid power



RF distribution layout for an 8-cavity cryomodule



J. Osborne – 2012 LHeC Meeting Chavannes

Disadvantages:

- Need for By-Passes at ATLAS and CMS
- Many other integration difficulties
- Would stop LHC running during its installation



From LHeC design report: Linacs

- 60 GeV
- Two 10 GeV Linacs, 0.3 GeV injection and 6 linac passes
- 6.6 mA beams

RF System

- 5-cell cavity at 20 MV/m (20.8 MV per cavity) 721.42 MHz
- Q_o = 2.5 E10
- 480 cavities per linac (960 in total)
- 60 cryomodules of ~ 15.5 m length per linac (990 m)
- One 21 kW rated (solid state) power source per ca
- RF and controls in separate tunnel
- 24 MW grid power for RF

Arc RF systems – if needed ..

- 1442/721 MHz 58/38 cavities
- 10.5 MW RF, 23 MW Grid power

Strong synergy with SPL

- R&D directly applicable to LHeC ERL
- And with BNL work for eRHIC at 704 MHz







- Motivation
 - Study behaviour of a high energy multi-pass multiple cavity ERL for LHeC
 - Namely Optics, RF power requirements, synchronization & delay issues ...
 - HOMs & HOM couplers, Cryogenics, instrumentation, controls, LLRF ...
 - Injector studies DC gun (JLAB) or SRF gun FZR Rossendorf, BNL
 - Reliability issues, operation issues
 - Could be foreseen as the injector to LHeC ERL ? (See E. Jensen's talk)
- Specs
 - High Energy ~0.5 GeV, and CW.
 - High beam current: 40 -100 mA?
 - At least 2 passes (optics studies, synchronization & delay issues)
 - Multi cavity cryomodule
 - Two Linac layout as LHeC ERL
- Other Physics Motivation:
 - ERL demonstration, FEL, γ-ray source, eCooling ? (@PS/SPS energies),
 - Ultra short electron bunches
- Potentially one of first low-frequency SC-ERL test facilities
 - Synergy with SPL-ESS, JLAB & BNL activities.





- Optimum frequency
 - 721 MHz a good choice gradients of ~20 MV/m can be achieved with good Qo
 Cryo power, HOMs, synergy with CERN R&D and other projects
- Highest Qo at medium gradients
 - BCP and/or electro-polishing recipes
 - Surface inspection (optical microscopy or by other means)
 - Diagnostics
 - All part of CERN SCRF activities and infrastructure upgrade
 - Encouraging news from JLAB Heat treatment at 1400 degrees Qo > 4E10 !!
 G. Ciovati et al.
 - Would reduce cryo consumption considerably compared to our estimated Qo of 2.5E10 in the DR !!
 - Further studies on this and other methods ..
- Studies of material other than bulk niobium e.g. Thin films ? Nb₃Sn ?
 - Sputtered coating would significantly reduce cost
 - Extensive studies at CERN (Quadrupole Resonator T. Junginger et. al.)
 - HiPIMS CERN effort ongoing with Legnaro/Sheffield First cavity tested at Legnaro recently !
 - Nb₃Sn could be studied at CERN (QR) in collaboration with other labs





- SCRF has played a major role in CERN's Flagship accelerators (LEP => LHC)
- But CERN has fallen behind in state-of-the art technology needed, and in research
- Several exciting & challenging new projects are now under way
- The SRF team at CERN is modest but the activities are growing steadily

• Collaboration to be strengthened with other Labs on SRF issues

=> cavity and component preparation, surface treatments, new materials, assembly procedures, tests and diagnostics, cryostat and cavity ancillary design.





Acknowledgements:

To the many members of the CERN's TE and EN departments for the work being done on design and fabrication of cavities and components, cavity preparation and treatment and cryomodule design in the context of the projects described

To collaborators in many laboratories around the world, e.g. SACLAY, DESY, INFN, Cockroft Institute, JLAB, SLAC, Fermilab, JLAB, ODU, TRIUMF, for their invaluable advice and collaboration.



"Common research Infrastructure for Synergies in Physics" For manpower support for Infrastructure upgrades, SPL and ISOLDE work.



For support for Crab Cavity activities

Thank you for your attention





Spare Slides





- Feasibility
 - SPL type CMs are being produced. Only minor frequency & coupler adjustment needed for LHeC
- Infrastructure
 - Need cryogenics, shielding, electricity, water, RF power, LLRF & Controls
- Location
 - SM18 or close to SM18 a first obvious suggestion, cryo availability, already has RF activity.
 - Cryo Capacity would be sufficient
 - Sharing of cryo ?
 - All equipment could be eventually be reused, for example on the injector site
- Timeline determined by
 - Availability of cryomodules in 2014 SPL cryomodule will be ready
 - Time to produce cryostat(s) and introduce 721 MHz cavities
 - 3 years a reasonable estimate ?
- Cost
 - TbD, but material for cryomodule construction ~ 2M CHF each (SPL F. Gerigk))