

LCLS-II & LCLS, too

November 12, 2012



Linac Coherent Light Source Facility First Light April 2009, Project Complete June 2010







Existing Linac (1 km) (with modifications)

Injector

Undulator (130 m

Transport

lear Experiment Hall

Far Experiment Hall

Typical operating parameters

X-RayTuning Range	280 - 10,000	eV
Peak Power	up to 70	GW
Bandwidth, 8,000 eV	0.2 typical; <0.01 seeded	% FWHM
Bandwidth, 800 eV	0.5 typical	% FWHM
X-Ray pulse duration	~3-500	x 10 ⁻¹⁵ sec
Beam size at waist, 800 eV	20, typical	μm, RMS
Beam divergence, 800 eV	20, typical	µrad, FWHM
Beam size at waist, 8,000 eV	15, typical	μm, RMS
Beam divergence, 8,000 eV	3, typical	µrad FWHM
Energy/Pulse	> 2 typical, 6 max	mJ
Energy Jitter/Pulse	5 typical	%
Pulse Repetition Rate	120	Hz

LCLS Experiment Stations Are Now Fully Operational



LCLS Operations Summary





SLAC



703 proposals (~15 scientists/proposal)

- > 31 countries
- > only 1 in 5 proposals gets beam time

~ 60% of papers in high impact journals

Beam delivery is ~95% of scheduled beam time

JLAB - 12 November 2012

Experiment Program is Oversubscribed



152 proposals for beam time between January and July, 2013

Lets Proposal Summary							
	Run 1	Run 2	Run 3	Run 4	Run 5	Run 6	Run 7
Proposals Received	Sept'08	<u>May '09</u>	<u>Nov'09</u>	<u>Jun'10</u>	<u>Jan'11</u>	Sept'11	Jul'1:
AMO	28	24	16	25	15	15	17
SXR		38	32	31	18	28	23
XPP			59	35	34	27	35
CXI				25	29	36	45
MEC					12	18	19
XCS					6	10	13
Total Proposals Received	28	62	107	116	114	134	152
	"User Assisted Commissioning"		Dedicated L				
	Run 1	Run 2	Run 3	Run 4	Run 5	Run 6	Run 7
Experiments Performed	Oct-Dec'09	May-Sep'10	Oct-Mar'11	Jun-Oct'11	Nov-May'12	Jun-Dec'12	Jan-Jul'1
AMO	11	13	5	7	4	7	5
SXR		10	5	6	4	5	7
XPP			11	6	9	8	11
CXI			4	6	8	7	12
MEC					2	4	4
XCS					2	2	3
Total Proposals Scheduled	11	23	25	25	29	33	42
% Proposals Scheduled	39%	37%	23%	22%	25%	25%	28%
Est. User Hours Requested	1680	3720	6420	6960	6840	8040	9120

LCLS Beam-Sharing Demonstration January 2013

Demonstration in operations targeted for Jan 2013

LCLS beamtime in very high demand

Increase capacity by multiplexing using large offset monochromators (LOM) with thin Bragg crystals

- Enables simultaneous operation of multiple instruments ٠
 - XPP/XCS or XPP/CXI or XCS/CXI or XPP/XCS/CXI
- Thin crystal choices ٠
 - Si 10 μm -
 - -vibrations a problem
 - diamond 100 µm
 - Latest tests look OK •





Etch processes:

<400>,<220>,<111>

- · Yiping Feng, Lead Physicist
- · Venkat Srinivasan, Lead Engineer
- Diling Zhu, Henrik Lemke,, Matthieu Chollet, Aymeric Robert, David Fritz, Jim Defever, Jerry Hastings, Paul Montanez, Joseph Robinson, Silke Nelson, Marcin Sikorski, Sanghoon Song (SLAC)

- Harald Sinn (EuXFEL)
- Yuri Shvydko, Stanislav Stoupin (APS)



Hard X-Ray Self-Seeding Tests at LCLS





Self-seeded operation of the LCLS hard X-ray FEL in the long-bunch mode Gianluca Geloni, Vitali Kocharyan, Evgeni Saldin DESY 10-239



"Seeded FEL Concept Possible application of X-ray optical elements for reducing the spectral bandwidth of an X-ray SASE FEL" J. Feldhaus, E.L. Saldin, J.R. Schneider, E.A. Schneidmiller, M.V. Yurkov, Opt. Comm. **140**, 341 (1997)

SXRSS Overview

27

First Demonstration of Hard X-ray Self Seeding at LCLS



SASE and Seeded spectra recorded on single shots. The left panels are SASE with 150 pC, 3kA peak current, un-seeded. The FWHM of the SASE spectrum is 0.2 % Bandwidth. The right panels are the seeded beam with the same electron beam parameters. The FWHM of the seeded beam is 0.5 eV (5x10⁻⁵ bandwidth)



Single shot pulse energy from the gas detectors with 40pC charge

- J. Amman, et al., "Demonstration of self-seeding in a hard-X-ray free-electron laser," Nature Photonics, DOI: 10.1038/NPHOTON.2012.180 (2012).
- The mean seeded FEL power is 8 GW with a 2.5 GW SASE background at 8 keV for 40 pC bunch charge.
- Peak seeded power is in excess of 15 GW, comparable to SASE but with a spectral bandwidth reduction by the factor of 40.
- Next steps include system optimization of the LCLS undulator beamline including additional undulators which should increase seeded power and reduce intensity fluctuation.



SLAC-Argonne-TISNCM Collaboration



Tested at XCS Beamline- Outperforms Best SASE Intensity



SASE after Si(111)

. .

<Gas det> =5mJ 4-6 spikes <I>mono =2V No FEE spectro

Seeded after Si(111)

<Gas det> =1mJ 4-6 spikes <I>mono =3.4V With FEE spectro

Correction FEE spectro =0.7

$$\frac{\langle I \rangle_{\text{seeded after Si(111)}}}{\langle I \rangle_{\text{SASE after Si(111)}}} = \frac{3.4/0.7}{2} = 2.4$$

Room in the LCLS tunnel for more undulators – "tapering" after seeding could yield ~ 0.4 TW in narrow BW

JLAB - 12 November 2012

s1 0

Soft X-Ray Self-Seeding

LCLS is developing a compact grating monochromator and chicane that is similar to HXRSS unit in size



Fit within the length of one undulator module 4 m.

Photon energy range 400 - 1000 eV.

- X-ray and electron delay varies from 660 850 fs.
- Resolving power from 7800 (400 eV) to 4800 (1000 eV).



P. Heimann

JLAB - 12 November 2012



X-band Transverse Cavity (XTCAV)

fs electron and x-ray temporal diagnostics - project started in FY11



Transverse cavity installed



Variable Phase Undulator for Polarization Control & Terawatt



- Four independent quadrants of permanent magnets move longitudinally at fixed gap.
- By sliding the arrays it is possible to control the K from full to zero
- and to control the polarization of the radiation emitted JLAB 12 November 2012

Multi Bunches – Multiple Lasers – Multiple User

- Two bunch lasing demonstrated 07/2010, 8.4 ns separation, 250 pC
- Single laser, 2 pulses from pulse stacker

- Two FEL demonstration with kinked undulator 01/2011
- Used slow kicker for 2x 5 Hz
- 2 bunches and fast kicker would enable 2x 120 Hz

Two bunches separated by TCAV3

Two X-ray pulses separated energy

Two bunches separated orbit

Two X-ray pulses separated transv







Overall Layout, LCLS-II

BC-1 moved downstream (375 MeV)

- Less energy jitter
- Compatible with future 360 Hz operation

YAG screens

- OTR screens
- Wire scanners
- Bunch length mon.



Enhanced Capability

LCLS-II will provide expanded spectral range

- Up to 13 keV (above Selenium K-edge) @ 10.5-13.5 GeV
- Down to 250 eV (Carbon K-edge) @ 7-10 GeV
- 302m undulator tunnel
 - Space to accommodate future enhancements:
 - Seeding
 - polarization control
 - TW peak power



Tuning the X-Rays with both undulator gap and Electron Beam Energy

Greater Capacity

- Dedicated injector at Sector 10
- Two new SASE undulator systems, both variable gap
- High Field Physics Soft X-Ray Experiment Station
- Sets the stage for
 - 3X increase in hours of operation for soft x-rays
 - Generally, soft x-ray experiments run one-at-a-time
 - ~15%-30% increase in operations hours for hard x-rays, even with no new HXR instruments
 - Since hard x-ray instruments will someday run simultaneously, perhaps
 2 or even 3 at a time, this can mean this much more time per station
- Future: Room in new experiment hall for up to 6 new instruments JLAB – 12 November 2012

LCLS-II Project Organization

LCLS-II Project Project Director - John Galayda Functional Organization – August 2012 Deputy Project Director - Dave Schultz External Committees PMOG Project Office - Richard Boyce **SLAC Directorate Liaisons** FAC AD - R. Hettel Associate Project Director for LCLS - J. Arthur Conventional Construction - Dave Schultz **Project Office** Richard M. Boyce ESH - J. Healy, I. Evans, M. Sharfenstein Financial Planner - A. Reese Quality Assurance - D. Marsh Project Controls - D. Sala, D. Rasalkar Admin. Support - H. O'Donnell / B. Hemstad Procurement - J. Davey / B. Miller Document Specialist - R. Rence **Electron Systems Physics Support** Photon Systems Integration & Conventional T. Raubenheimer Coordination Facilities Jose Chan Michael Rowen T. Raubenheimer - Injector, Linac Lori Plummer Robert Law Z. Huang - FEL J. Welch - XTOD Injector H.D. Nuhn - Undulator Undulator G. Hays S. Marks - LBNL P. Heimann - Photon Systems Sector 10 Inj W. Olson - SLAC Vacuum - D. Gill Bldg. Controls - H. Shoaee PM - D. Saenz Linac Diagnostics - H. Loos D. Hanguist XTOD Rad. Phys. - M. Santana E. Ortiz Elect. Sys. - P. Rodriguez Heavy Civil Laser Sys. - G Hays Constr. Controls/ Power Conversion - B. Lam PM - Jess Albino **Global Systems** RF Sys. - V. Pacak XES H. Shoaee Metrology - C. LeCocq A. Busse Mech. Sys. - J. Amann Safety Sys. - F. Tao Facilities - B. Law AD Tech Planning - K. Ratcliffe

JLAB - 12 November 2012

Funding/Schedule Overview

	FY	FY	FY	FY	FY	FY	FY	FY	
Fiscal Year	10	11	12	13	14	15	16	17	Total
OPC and Pre-Ops	\$1.2	\$9.4	\$8.0		\$0.7		\$0.7		\$20.0
LLP			\$20.0	\$20.0					\$40.0
Design/ Construction			\$ 2.0	\$43.5	\$80.3	\$94.0	\$105.3	\$19.9	\$345.0
Total Project Cost	\$1.2	\$9.4	\$30.0	\$63.5	\$81.0	\$94.0	\$106.0	\$19.9	\$405.0

New funding profile guidance: +14.7 +\$10.0

-\$4.8 -\$19.9

SI AC

Loval I Pacolina Milastonas	Sabadula
	Schedule
CD-0, Approve Mission Need	4/22/10 (actual)
CD-1, Approve Alternative Selection and Cost Range	10/14/11 (actual)
CD-3a, Approve Long Lead Procurement Baseline and	
Start of Long Lead Procurements	3/14/2012 (actual)
CD-2, Approve Performance Baseline (Review 8/21-23)	10/31/2012
CD-2/CD-3b, Approve Start of Construction	6/30/2013
CD-4, Approve Project Completion	9/30/2019

JLAB – 12 November 2012

New Guidance on Funding Profile

	FY	FY	FY	FY	FY	FY	FY	FY	
Fiscal Year	10	11	12	13	14	15	16	17	Total
OPC and Pre-Ops	\$1.2	\$9.4	\$8.0		\$0.7		\$0.7		\$20.0
LLP			\$20.0	\$20.0					\$40.0
Design/ Construction			\$ 2.0	\$43.5	\$95.0	\$104.0	\$100.5	\$0	\$345.0
Total Project Cost	\$1.2	\$9.4	\$30.0	\$63.5	\$95.7	\$104.0	\$101.2	\$0	\$405.0

CF Construction:

- Should enable acceleration of schedule
 - Undulators, x-ray optics and x-ray experimental systems are candidates for acceleration
 - May gain 6 months on "First Light" milestone













LCLS-II Schedule - 6-month LCLS outage



Post-down work: Finish BTH2 concrete Finish FEE & EH2 concrete Construct EH2 2nd floor <u>6-month down work:</u> Utility relocation UH tunneling from the west BTH2 concrete construction Excavate UH2 Access Shaft

Excavate EH2 cavern Tunnel FEE & Maze UH and EBD concrete Linac installation in LCLS areas Pre-down work: Site work Start Access Tunnel

Vibration studies with LCLS operating, Aug. 1st

★ Used a road header, backhoe, jack hammer, concrete vibrator, concrete drill, and truck traffic



- Instrumented area with 20 accelerometers and seismometers
- No effect seen on SPEAR beams
- 1 No effect seen on LCLS electron beam
- 2 No effect seen of LCLS x-ray beam at FEE direct imager
- **3** No distinguishable effect seen at XCS experiment in the FEH
 - Other effects may mask any construction-driven beam motion
- Impulses detected on FEE & XRT mirrors under analysis

LCLS-II Long-Lead Acquisitions: Construction Underway

- CD-3a (2 x \$20M in 2012-2013) approved for:
 - 135 MeV Injector + new annex building at Sector 10
 - Injector fabrication underway
 - Operational during 2015-2016
 - R&D supporting LCLS
 - Connect to LCLS-II linac in 2016
 - Hard x-ray undulator magnet blocks
 - Partial order (1/4 of total)
 - Larger purchase if contingency permits

SI AC

LCLS RF Gun in fabrication



Photocathode Laser- will be identical to many lasers in use now at LCLS



Copper cathode: QE>1x10⁻⁴, 2X original design spec lifetime: years



Injector & Laser Heater, Same as LCLS



JLAB - 12 November 2012

Sector 10 Laser Annex Construction Underway





LCLS-II Linac BC1 and BC2, Extensive Re-Use of Designs



JLAB – 12 November 2012

LCLS-1 Bypass, Re-Use PEP-II Transport Line



Undulators Designed & Acquired by





JLAB - 12 November 2012

X-Ray Transport, Optics & Diagnostics X-Ray Experiment Systems

• Based on proven LCLS and LUSI designs



JLAB – 12 November 2012

XES

X-ray Experimental Systems (XES):

- Design and build a high field Soft X-ray experimental system
 - Components based on XTOD & LCLS-I
- The high field experimental system provides focused, high-intensity soft x-rays for:
 - Studies of non-linear x-ray physics and other Atomic, Molecular and Optical (AMO) science
 - Single-particle imaging experiments from the water window up to 2000eV
 - Use LCLS sample chambers



4

LCLS-II Accelerator for 250 pC, 120 Hz



Injector, linac, and compression parameters are all very similar to LCLS-I, but not exact JLAB – 12 November 2012

Differences between LCLS-I and LCLS-II

The LCLS-II design is heavily based on the LCLS-I

- Primary differences
 - Six fewer rf stations than LCLS-I
 - Roughly 1.5 GeV lower voltage, ok with lower bunch charge
 - 1.2km of additional drift in bypass line
 - Larger chirp at linac end \rightarrow understand wakefields
 - Two undulator beamlines HXR and SXR
 - Beamline separation with kicker and septum
 - Variable gap undulators
 - Can decouple photon energy from beam energy
- Lots of smaller changes based on LCLS-I experience

LCLS-II Beam Emittances Based on LCLS-I Operation

Better performance with lower charge

- LCLS-I was optimized for 1 nC and 1 mm-mrad but now routinely operates with 150 pC and slice emittances less than 0.3 mm-mrad
- LCLS-II will be optimized around 250 pC and 0.4 mm-mrad → shorter gain lengths and undulators than in LCLS-I original design



Alternate Optics layout Modified LTUS – Eases 2-bunch upgrade



JLAB - 12 November 2012

Work by Yuri Nosochkov

C

Baseline Undulator Configuration Optimized for 250 pC

Baseline undulators have been chosen to saturate with 250 pC across photon wavelength range:

HXR: 2 – 13 keV and SXR: 0.25 – 2 keV

- 15% overhead in SXR undulator length at 250 pC
- Little overhead or margin in HXR baseline at 250 pC

Photon Energy (keV)	Beam Energy (GeV)	Charge (pC)	Emittance (mm-mrad)	Saturation Length (m)	
13	13.5	250	0.4	87 ←	- Baseline
13	13.5	150	0.3	75	
13	12.3	150	0.3	74	

Rapid reduction of gain length with charge and $\gamma\epsilon$

• 250 pC \rightarrow 150 pC estimated to reduce gain length by ~15%

SI AC

Understand Possible LCLS-II Upgrades Recommendation from LCLS-II CD-1 Review

Understand upgrades to avoid preclusion

- Upgrades may bundled with follow-on instrument project or may come as AIPs
- Also consider if early inclusion can be accommodated with acceptable cost and risk

Possible upgrades include:

- Polarization control
- Multi-bunch and/or higher repetition rate operations
- Self-seeding and Two-bunch seeding
- Terawatt XFEL

LCLS-I R&D will further develop possible options

Polarization and Multi-Bunch Operation



- LCLS-I R&D program to develop DELTA undulator for polarization control
 - Space left at end of SXR for 3 DELTA undulator segments
- Three multi-bunch configurations considered:
 - Bunches to both undulators @ 120 Hz (>30 ns separation)
 - Bunch pairs for 2-bunch self-seeding (few ns separation)
 - Bunch train (up to 30 bunches with ~10 ns spacing)
 - Studying wakefield limitations and energy control
 - Shielding designed for 5 kW beam power
 - Up to 30 bunches of up to 100 pC per rf pulse
 - Will require improvements to diagnostics, gun and laser

Seeding Options Bandwidth limited Operation

Improving understanding of options for hard and soft x-ray seeding

Experiment on HXRSS installed in LCLS-I \rightarrow user operation



Developing plans for similar SXRSS experiment

Working on options for two-bunch seeding

- Pro: works over wider range of wavelength and bunch parameters → greater flexibility, more x-ray power
- Con: more complicated

FEL TW Physics with Strong Tapering Little experience; extensive simulation study





 Working to understand saturation mechanisms and tolerance implications

Extended Undulator Hall Enable Terawatt (TW) Upgrade



Many S-2-E studies to understand requirements

- Need roughly 270 meters of undulator for 13 keV
- Extended undulator hall has room for 282 meters of undulator

FEL energy (keV)	SASE Undulator Portion (m)	Saturation Full Length (m)	Power (TW) 200 m Full undulator	Power (TW) 250 m Full undulator	Power (TW) 300 m Full undulator
8	39	220	1.1	1.1	1.1
13	43	270	0.8	1.3	1.4
18	48	330	0.5	0.7	0.9

• Extended hall also allows for 2-color generation or other options

Closing Comments

- Design of LCLS-II is well advanced
 - The necessary documentation is ready for CD-2
- LCLS-I lessons learned have been incorporated
 - Parameters based on LCLS-I operation
 - Documented LCLS-I beam physics lessons learned for Injector, Linac and LTU
- Some details to still complete (e.g., balancing tolerance studies, performance across full operational space, ...)
- Studying expansion upgrades to avoid preclusion
 - LCLS-I R&D program will further clarify options

LCLS-II is just the start...

Concepts for new instruments are being developed Downselect and instrument construction schedule TBD

- "Hard" x-rays
 - Nanocrystallography, 6-13 keV
 - 2 stations, one for imaging and one for screening crystals
 - Stations in series, x-ray beam will be re-focused
- Hard x-ray general purpose
 - Pump/probe, harder x-ray spectrum
- Soft x-rays 250-2,500 eV
 - High-Field Physics (in LCLS-II Scope)
 - Monochromatic (< 10⁻⁵) station
 - Nonlinear/quantum soft x-ray optics



End of Presentation

